



SECTION A-A

Remark:

1. The foundation and the support of center sump are at the same level.
2. The height deviation should less than 1/4".
3. Final foundation design must be determined considering the pump's NPSHR.
4. Location of anchors is approximate and final location must be verified on-site by the installer.



PROJECT / MODEL

MCC-08A FOUNDATION

TITLE

MESAN COOLING TOWER

DRAWN BY DESIGNED BY CHECKED BY APPROVED BY

KING MING MING ISA

SCALE FILE NAME DATE

2014-01-05

DRAWING NO. REVISION

MCC-08A-F

01