



**Remark:**

1. The foundation and the support of center sump are at the same level.
2. The height deviation should less than 1/4".
3. Final foundation design must be determined considering the pump's NPSHR.
4. Location of anchors is approximate and final location must be verified on-site by the installer.



PROJECT / MODEL

# MCC-09B FOUNDATION

TITLE

## MESAN COOLING TOWER

DRAWN BY DESIGNED BY CHECKED BY APPROVED BY

KING MING MING ISA

SCALE FILE NAME DATE

2014-01-05



DRAWING NO. REVISION

MCC-09B-F

01

**SECTION A-A**

≥400mm  
[≥1'-3 3/4"]  
The height of the foundation should be set according to the water outlet pipe diameter.