


- Remark:
- 1、 The foundation and the support of center sump are at the same level.
  - 2、 The height deviation should be less than 1/4" .
  - 3、 Final foundation design must be determined considering the pump's NPSHR.
  - 4、 The operating weight is 3715lbs .

				
PROJECT / MODEL				
MKT-100				
FOUNDATION				
TITLE				
MESAN COOLING TOWER				
DRAWN BY	DESIGNED BY	CHECKED BY	APPROVED BY	
xin	xin	Alice	Isa	
SCALE	FILE NAME		DATE	
			2012-05-03	
DRAWING NO.				
REVISION				
			01	