



The height of the foundation should be set according to the water outlet pipe diameter.

Remark:

- 1、 The foundation and the support of center sump are at the same level.
- 2、 The height deviation should be less than 1/4" .
- 3、 Final foundation design must be determined considering the pump's NPSHR.
- 4、 The operating weight is 44 1lbs .



PROJECT / MODEL

MKT-12
FOUNDATION

TITLE

MESAN COOLING TOWER

DRAWN BY DESIGNED BY CHECKED BY APPROVED BY

xin xin Alice Isa

SCALE FILE NAME DATE

2012-05-03

DRAWING NO. REVISION

01

