



- Remark:
- 1、 The foundation and the support of center sump are at the same level.
 - 2、 The height deviation should less than 1/4".
 - 3、 Final foundation design must be determined considering the pump's NPSHR.
 - 4、 The operating weight is 6173lbs。



PROJECT / MODEL

**MKT-150
FOUNDATION**

TITLE

MESAN COOLING TOWER

DRAWN BY	DESIGNED BY	CHECKED BY	APPROVED BY
xin	xin	Alice	Isa
SCALE	FILE NAME	DATE	
		2012-05-03	
DRAWING NO.	REVISION		
	01		

