


- Remark:
- 1、 The foundation and the support of center sump are at the same level.
  - 2、 The height deviation should be less than 1/4".
  - 3、 Final foundation design must be determined considering the pump's NPSHR.
  - 4、 The operating weight is 7485lbs.

				
PROJECT / MODEL				
MKT-200				
FOUNDATION				
TITLE				
MESAN COOLING TOWER				
DRAWN BY				
DESIGNED BY		CHECKED BY		APPROVED BY
xin	xin	Alice	Ilsa	
SCALE		FILE NAME		DATE
				2012-05-03
DRAWING NO.		REVISION		01
