



Remark:

- 1、 The foundation and the support of center sump are at the same level.
- 2、 The height deviation should less than 1/4" .
- 3、 Final foundation design must be determined considering the pump's NPSHR.
- 4、 The operating weight is 20260 lbs. °



PROJECT / MODEL

**MKT-450
FOUNDATION**

TITLE

MESAN COOLING TOWER

DRAWN BY DESIGNED BY CHECKED BY APPROVED BY

xin xin Alice

Isa

SCALE FILE NAME

DATE

2012-05-03

DRAWING NO.

REVISION

01

