



The height of the foundation should be set according to the water outlet pipe diameter.

- Remark:
- 1、 The foundation and the support of center sump are at the same level.
 - 2、 The height deviation should less than 1/4".
 - 3、 Final foundation design must be determined considering the pump's NPSHR.
 - 4、 The operating weight is 2249lbs.



PROJECT / MODEL

MKT-60

FOUNDATION

TITLE

MESAN COOLING TOWER

DRAWN BY DESIGNED BY CHECKED BY APPROVED BY

xin xin Alice

Isla

SCALE FILE NAME

DATE

2012-05-03

DRAWING NO.

REVISION

01

