


Remark:

- 1、 The foundation and the support of center sump are at the same level.
- 2、 The height deviation should be less than 1/4".
- 3、 Final foundation design must be determined considering the pump's NPSHR.
- 4、 Location of anchors is approximate and final location must be verified on-site by the installer.
- 5、 The cooling tower foundation is designed and manufactured by customer.

			
PROJECT / MODEL			
<h1>MXC-03 FOUNDATION</h1>			
TITLE			
<h2>MESAN COOLING TOWER</h2>			
DRAWN BY	DESIGNED BY	CHECKED BY	APPROVED BY
MING	MING	ISA	ISA
SCALE	FILE NAME		DATE
			2012.12.01
	DRAWING NO.	REVISION	
	MXC-03-F	01	