


- Remark:**
- 1、 The foundation and the support of center sump are at the same level.
 - 2、 The height deviation should be less than 1/4" .
 - 3、 Final foundation design must be determined considering the pump's NPSHR.
 - 4、 Location of anchors is approximate and final location must be verified on-site by the installer.
 - 5、 The cooling tower foundation is designed and manufactured by customer.



PROJECT / MODEL
**MXC-07
FOUNDATION**

TITLE
MESAN COOLING TOWER

DRAWN BY MING	DESIGNED BY	CHECKED BY	APPROVED BY
SCALE	FILE NAME	DATE	REVISION
	MXC-07-F	2012.12.01	01