


The height of the foundation should be set according to the water outlet pipe diameter.

- Remark:**
- 1、 The foundation and the support of center sump are at the same level.
 - 2、 The height deviation should be less than 1/4".
 - 3、 Final foundation design must be determined considering the pump's NPSHR.
 - 4、 The operating weight is 2513lbs.

			
PROJECT / MODEL			
MKT-70			
FOUNDATION			
TITLE			
MESAN COOLING TOWER			
DRAWN BY	DESIGNED BY	CHECKED BY	APPROVED BY
xin	xin	Alice	Isa
SCALE	FILE NAME		DATE
			2012-05-03
	DRAWING NO.	REVISION	
		01	