


The height of the foundation should be set according to the water outlet pipe diameter.

- Remark:
- 1、 The foundation and the support of center sump are at the same level.
 - 2、 The height deviation should be less than 1/4" .
 - 3、 Final foundation design must be determined considering the pump's NPSHR.
 - 4、 The operating weight is 1620lbs .

			
PROJECT / MODEL			
MKT-35			
FOUNDATION			
TITLE			
MESAN COOLING TOWER			
DRAWN BY	DESIGNED BY	CHECKED BY	APPROVED BY
xin	xin	Alice	Isa
SCALE	FILE NAME	DATE	
		2012-05-03	
	DRAWING NO.	REVISION	
		01	