


The height of the foundation should be set according to the water outlet pipe diameter.

- Remark:**
- 1、 The foundation and the support of center sump are at the same level.
 - 2、 The height deviation should be less than 1/4" .
 - 3、 Final foundation design must be determined considering the pump's NPSHR.
 - 4、 The operating weight is 16248 lbs. .

| | | | |
|---|-------------|------------|-------------|
|  | | | |
| PROJECT/MODEL MKT-330 FOUNDATION | | | |
| TITLE MESAN COOLING TOWER | | | |
| DRAWN BY | DESIGNED BY | CHECKED BY | APPROVED BY |
| xin | xin | Alice | Isa |
| SCALE | FILE NAME | DATE | REVISION |
| | | 2012-05-03 | 01 |
| DRAWING NO. | | REVISION | |