



The height of the foundation should be set according to the water outlet pipe diameter.

- Remark:
- 1、 The foundation and the support of center sump are at the same level.
  - 2、 The height deviation should be less than 1/4".
  - 3、 Final foundation design must be determined considering the pump's NPSHR.
  - 4、 The operating weight is 2513lbs.



PROJECT/MODEL  
MKT-70  
FOUNDATION

TITLE  
MESAN COOLING TOWER

DRAWN BY	DESIGNED BY	CHECKED BY	APPROVED BY
xin	xin	Alice	Isa
SCALE	FILE NAME	DATE	
		2012-05-03	
	DRAWING NO.	REVISION	
		01	