


The height of the foundation should be set according to the water outlet pipe diameter.

- Remark:
- 1、 The foundation and the support of center sump are at the same level.
  - 2、 The height deviation should be less than 1/4".
  - 3、 Final foundation design must be determined considering the pump's NPSHR.
  - 4、 The operating weight is 39595 lbs.

			
PROJECT/MODEL			
MKT-800			
FOUNDATION			
TITLE			
MESAN COOLING TOWER			
DRAWN BY	DESIGNED BY	CHECKED BY	APPROVED BY
xin	xin	Alice	Isa
SCALE	FILE NAME		DATE
			2012-05-03
	DRAWING NO.	REVISION	
		01	